

DATE: November 26, 2012
TEST NO: 1

COMPANY DETAILS:

Company Name: Shajar Capital Pvt Ltd
Contact Person: Mr. Adnan Ali Khan
Designation: Head of IT
Address: P&O Building, Main I.I. Chundrigar Road
Contact Details:

INSTALLATION DETAILS:

Make: Galanz
Type: Split
Capacity: 2 Ton
Line Voltage: 220 V, Single Phase

TEST RESULTS

Without AircoSaver

	Date	Time	Temp	Units
Start	22 NOV	10:24	20°C	178.591
Stop	22 NOV	12:24	20°C	183.655
Total		2:00		5.064

Units Consumed per Hour: 2.532

With AircoSaver

	Date	Time	Temp	Units
Start	22 NOV	16:07	20°C	183.858
Stop	22 NOV	18:07	20°C	187.827
Total		2:00		3.969

Units Consumed per Hour: 1.984

SAVINGS in KWH: 0.548

SAVINGS in %: 21.64%



CLIENT ACKNOWLEDGEMENT

FOR ENERTECH